

# h-line

## Kit HL-WK73

### H-LINE

This h-line lightweight modular display system is designed to work within a 10 x 30 inline booth space. The simple no tools required setup uses the Build by Numbers™ assembly system. The full height aluminum frame modules are skinned using a dye-sub printed SEG fabric graphic that are easily changed out. At the far left is a provision for up to a 42" surface mounted monitor and behind that an enclosed storage area. The stepped back wall helps create visual impact while allowing for a break in messaging or branding. The forward return side walls help separate the exhibit from neighbors. All visible backwall, return, and sidewalls are covered with high impact SEG fabric graphics. The full sized modules ship in a slotted traditional trade show crate.

#### FEATURES

- Lightweight full height aluminum modules make assembly quick
- Lifetime warranty on hardware
- High impact dye-sub SEG fabric graphics are easily changed out
- Unit is easily reconfigured for different booth needs
- No tools required to assemble
- Lightweight framework and graphics equal shipping savings
- Components ship common carriers in a slotted traditional trade show crate



#### INCLUDES

- (14) HL-HMS038: 38" x 93" Frame w/ Graphic
- (2) HL-HMS138: 38" x 46.5" Frame w/ Graphic
- (2) HL-GRA138: 38" x 46.5" Graphic
- (2) HL-GRA038: 38" x 93" Graphic
- (2) HL-HMS019: 19" x 93" Frame w/ Graphic
- (1) HL-GRA019: 19" x 93" Graphic
- (1) HL-HMS119: 19" x 46.5" Frame w/ Graphic
- (1) HL-HMP019: 19" Door w/ Graphic
- (2) HL-HMS009: 9.5" x 93" Frame w/ Graphic
- (10) HL-HMS001: 3.15" x 93" Angled Pole w/ Graphic
- (1) HL-MM011-01: Media Mount
- (7) HL-DSFOOT: Double Sided Foot
- (1) CRATE

Price     \$19,120.00

*Carpet, Furniture and A/V not included*

# TECHNICAL SPECIFICATIONS\*

## Kit HL-WK73

H-LINE

### SIZE & WEIGHT

#### CRATE

Quantity	2
Container Size	46" L X 48" W X 100" H
Shipping Type	Freight
Shipping Weight	1500 Lbs
Exhibit Weight	380 Lbs

### ELECTRICAL REQUIREMENTS

Drops	1
Power (Amperage)	15

### ASSEMBLY TIME

Setup	3 Man Hours
Dismantle	1.5 Man Hours

